

SPECIFICATION OF MATERIALS

Sl. No.	Description of the Work	Qty	Unit	Unit Rate in Rs.		Total Amount in Rs.	
				Supply	Erection	Supply	Erection
1)	Supply, Installation, Testing and Commissioning of CP Plus 4 MB IP camera with 30 M dual light human detect colour image in night time.	20	No.				
2)	Supply, Installation, Testing and Commissioning of 6 TB surveillance Hard Disc Drive.	2	No.				
3)	Supply, Installation, Testing and Commissioning of CP plus 8 port Gigabyte POE switch with 2 gigabyte uplinks with rack.	3	No.				
4)	32 Channel NVR H.265, 8 MP support, 2 SATA HDD double slot 8 TB, HDMI,VGA output, mobile monitoring 12 VB DC 15 W.	1	No.				
5)	Connectors and back box.	20	SET				
6)	Supply, Installation, Testing and Commissioning of CAT-6 non armoured indoor cable for transmitting video signal and camera power cable (from camera to switch and switch to NVR).	1500	Mtrs				
7)	Supply, Installation, Testing and commissioning of wireless Mouse Logitech.	1	Nos.				
8)	Supply, Installation, Testing and Commissioning of outdoor box for switch.	3	Nos.				
9)	Electrical Materials	1	LOT				
10)	32" LED TV with stand	1	No.				
11)	HDMI cable 10 Mtrs.	1	No.				
	Sub total						
	GST 18%						
	Total amount						

Sd./ (29.09.26)

**Executive Engineer/Operation
400 KV Pulianthope GIS SS
Chennai-12.**